## City of Calimesa

# County Line Road Interchange Funding Summary

### January 30, 2018

Funding Source		Amount	% Total				
State Share							
TCEP Grant Funds	\$	6,160,000	70.0%				
Non-State Share							
City of Calimesa Funds	\$	1,320,000	15.0%				
City of Yucaipa Funds	\$	1,320,000	15.0%				
	-						

Total: \$ 8,800,000 100%

### City of Calimesa County Line Road Interchange

### Cost Share Summary

### January 30, 2018

Cost Category	Cost Summary		TCEP Grant Funds <sup>1.)</sup>		City of Calimesa Funds <sup>2.)</sup>		City of Yucaipa Funds <sup>3.)</sup>	
Project Approval/ Environmental Documents	\$	2,000,000	\$	1,400,000	\$	300,000	\$	300,000
Plans/Specifications/ Estimates/Const. Management	\$	1,500,000	\$	1,050,000	\$	225,000	\$	225,000
Right-of-Way	\$	1,570,000	\$	1,099,000	\$	235,500	\$	235,500
Construction	\$	3,730,000	\$	2,611,000	\$	559,500	\$	559,500
Total:	\$	8,800,000	\$	6,160,000	\$	1,320,000	\$	1,320,000
Cost Share:		100.0%	.0% 70.0%		15.0%		15.0%	

#### City of Calimesa

### **County Line Road Interchange Preliminary Construction Cost Estimate**

#### January 30, 2018

DI-	December to the	0	l locit	Unit Cook	0 t
No.	Description	Quantity	Unit	Unit Cost	Amount
1	Mobilization	1	LS	\$ 160,000	\$ 160,000
2	Environmental Mitigation	1	LS	\$ 50,000	\$ 50,000
3	SWPPP	1	LS	\$ 40,000	\$ 40,000
4	Remove Existing Roadway	124,304	SF	\$ 1.00	\$ 124,304
5	Clearing and Grubbing	1	LS	\$ 50,000	\$ 50,000
6	Earthwork	8,895	CY	\$ 8.00	\$ 71,160
	Earthwork (Import)	2,216	CY	\$ 12.00	\$ 26,592
	Construct 8" PCC Curb and Gutter	3,794	LF	\$ 18.00	\$ 68,297
1	Construct 8" PCC Curb Rolled Curb and Gutter	557	LF	\$ 20.00	\$ 11,131
2	Construct 8' PCC Sidewalk	7,934	SF	\$ 4.00	\$ 31,737
3	Construct 4" Decorative PCC	14,692	SF	\$ 10.00	\$ 146,916
4	Construct PCC Truck Apron	7,884	SF	\$ 10.00	\$ 78,840
5	Construct 0.15' AC Overlay	2,085	TONS	\$ 95.00	\$ 198,036
6	Construct 0.20' AC Base Pavement	2,779	TONS	\$ 90.00	\$ 250,151
7	Construct Crushed Misc. Base Variable Thickness (0.40' min.)	2,840	CY	\$ 65.00	\$ 184,587
8	Private Improvement Restoration	5	EA	\$ 25,000	\$ 125,000
9	Drainage Improvements	1	LS	\$ 200,000	\$ 200,000
10	Erosion Control	1	LS	\$ 15,000	\$ 15,000
10	Retaining Walls	200	LF	\$ 200.00	\$ 40,000
11	Barriers and Guardrails	1	LS	\$ 15,000	\$ 15,000
12	Landscape and Irrigation	6,913	SF	\$ 8.00	\$ 55,302
13	Utility Relocation	1	LS	\$ 150,000	\$ 150,000
14	Lighting and Electrical	1	LS	\$ 250,000	\$ 250,000
15	Signing and Striping	1	LS	\$ 150,000	\$ 150,000
16	Traffic Control and Construction Staging	1	LS	\$ 450,000	\$ 450,000

Construction Subtotal: \$ 2,942,054

Construction Contingencies (10%): \$ 294,205 Construction Total: \$ 3,240,000

Caltrans Processing (PSR-PDS): \$ 500,000

Caltrans Processing (PA&ED): \$ 1,500,000 Caltrans Processing (PS&E): \$ 1,500,000

Right-of-Way Acquisition: \$ 1,570,000

Construction Admin. and Engineering (15%): \$ 486,000

Project Total: \$ 8,800,000

70% Grant \$ 6,160,000 30% Local Match \$ 2,640,000

\$ 8,800,000